

Search for Muon to Electron Conversion at J-PARC: COMET Phase-I Experiment



MyeongJae Lee
(Institute for Basic Science, Korea)

Aug 5, 2016, ICHEP






Muon Conversion: $\mu^- N \rightarrow e^- N$




Signal

- Muon stops at Al (or Ti) target, captured in 1s orbit
- Decay with mono-energetic electron
 - $E = m_\mu - E_{\text{rec}} - E_B \sim 105 \text{ MeV}$




Background

- Decay-In-Orbit (DIO)



- Prompt background (to beam arrival)
 - Muon/pion decay in flight
 - Radiative pion capture: $\pi N \rightarrow \gamma X; \gamma \rightarrow e^+ e^-$
 - Cosmic, Anti-proton...

COMET Experiment



COMET Phase-II


For $R \sim 10^{-17}$ muon conversion measurement

- 56 kW proton beam
- 1 year DAQ

Detector Section

A detector to search for muon-to-electron conversion process

COMET Experiment



COMET Phase-II

For $R \sim 10^{-17}$ muon conversion measurement


- 56 kW proton beam
- 1 year DAQ

COMET-Phase-I

For BG measurement, $R \sim 10^{-15}$ muon conversion

- 3kW proton beam
- Half year DAQ

Facility / Beams



proton



Target prototype


pion






Transport solenoid
(Apr 2015)

- 8GeV, 3.2kW pulsed proton beam
- 4/9 (or 3/9) buckets filled in MR

Pion/Muon
to detector





Pulsed proton beam




One MR cycle : 2.48sec

- Pulsed proton beam
 - Beam background with proton pulse is major BG hit source
 - High extinction between beam enables localizing signal event in time
- $<10^{-9}$ extinction factor achievable by increasing MR RF voltage (May 2014), both at 8GeV and 30GeV

Cylindrical Detector system





- All stereo-wire drift chamber, 20 layers, ~ 5000 sense wires
- Hodoscope for timing and trigger
 - Trigger : see page 8
 - Timing requirement 1ns, $< 0.8\text{ns}$ could be achieved




Distribution of Timing difference between Cerenkov and Scintillator

CyDet construction





- Construction completed June 2016, Cosmic ray test from August 2016
- Spatial resolution requirement 200 μ m can be possible both gas mixture



Position resolutions of CDC prototype obtained in the beam test @Spring-8

CTH: Trigger Hodoscope





- Twisted, overlapped two scintillators + two Cerenkov detectors
- Primary hit rate too high for trigger

	Upstream Scintillator	Upstream Cherenkov	Downstream Scintillator	Downstream Cherenkov
Average rate @200 ~ 1170 ns (MHz)	3.5	1.5 - 2	4	3


- Adding lead shielding, require 4-fold coincidence for trigger
: **primary trigger rate 20 – 30 kHz**

Trigger / DAQ

- Still high trigger rate (20-30 kHz) for DAQ
 - Mostly background hits
 - Beam electron, secondary from capture neutron/gamma
- Using online BDT to suppress BG
 - Energy deposition in CDC, layer information as input to BDT
 - 95% BG suppressed, 99% signal electron retains
 - 1 – 2 kHz trigger rate achievable



COTTRI
for online trigger
implementation



FC7 (CMS)



FCT






RECBE (Belle-II)






Cosmic ray / Neutron



- To suppress Cosmic Ray muon to factor of 10^{-4}
 - Decay in flight, interaction with detector material
 - Note: CDC can full-reconstruct CR
- Neutron issue
 - SiPM weak to neutron irradiation, generates noise at Strip sensor
 - Internal Neutron Shield reduces neutron from stopping target
 - Similar neutron flux expected from proton target, shielding around beamline under study



Background measurement




- StrEcal
 - Detector for Phase-II
 - 5 station of straw detectors+ ~2000 LYSO calorimeter
- Beam measurement program at Phase-I
 - Particle composition, beam profile
 - 1/1000 reduced beam
 - no radiation tolerance, pile-up issue.
 - CyDet rolls out and StrEcal installed



Physics sensitivity

- Net acceptance = 4.1%
 - Online efficiency ~ 0.99
 - Geometric acceptance + track quality ~ 0.18
 - $103.6 \text{ MeV} < p < 106 \text{ MeV} : 0.93$
 - $700 \text{ ns} < t < 1170 \text{ ns} : 0.3$
- Background = 0.032
 - RPC ~ 0.003
 - DIO ~ 0.01
 - Cosmic < 0.01
- SES(Phase-I) $\sim 3.1 \times 10^{-15}$
 - SES(Phase-II) $\sim 2.5 \times 10^{-17}$




Type	Background	Estimated events
Physics	Muon decay in orbit	0.01
	Radiative muon capture	0.0019
	Neutron emission after muon capture	< 0.001
	Charged particle emission after muon capture	< 0.001
Prompt Beam	* Beam electrons	
	* Muon decay in flight	
	* Pion decay in flight	
	* Other beam particles	
	All (*) Combined	≤ 0.0038
	Radiative pion capture	0.0028
Delayed Beam	Neutrons	$\sim 10^{-9}$
	Beam electrons	~ 0
	Muon decay in flight	~ 0
	Pion decay in flight	~ 0
	Radiative pion capture	~ 0
	Anti-proton induced backgrounds	0.0012
Others	Cosmic rays [†]	< 0.01
Total		0.032

[†] This estimate is currently limited by computing resources.


Schedules

- Highly recognized by KEK IPNS, ready for stage-2 approval
- Proton beam line construction complete in 2017
- Phase-I physics data taking in 2018 or 2019
 - Cosmic run at 2018, 4 weeks of engineering run
 - 5 month data taking
- Phase-II R&D in parallel with Phase-I R&D and data taking
- Phase-II physics data taking in 2021
 - 1 year data taking



Summary

- **SES : 3.1×10^{-15}**
 - SES (Phase-II): 2.5×10^{-17}
- Start data taking at **2018**
- Half year data taking for
 - Muon conversion measurement
 - Beam measurement



176 collaborators,
33 institutes, 15 countries

