

大阪大学
The University of Osaka

Status of the COMET Experiment



Ryo Nagai

The University of Osaka

On behalf of the COMET Collaboration

Muon-to-Electron Conversion ($\mu^- N \rightarrow e^- N$)



Physics Briefing Book : Input for the ESPPU 2020 (CERN-ESU-004)



However, $\mu N \rightarrow e N$ is not so easy...
Sensitivity is built by beam control,
not only by detectors

Search for μ -e conversion in an atom

- Decay-in-Orbit (DIO)
— *main background, irreducible*



Excellent momentum resolution is a key


- Beam-Related Backgrounds

- Using pulsed beam
- Delaying signal using the muonic-atom lifetime in Al

→ Reduce beam BG

- Cosmic-ray Backgrounds

- Due to the rare event search, cosmic ray contribution is **not negligible**
- high-energy electrons & muons from CRs mimicking the signal
→ vetoed by surrounding CRVs




COMET Experiment Concept



Search for $\mu^- \rightarrow e^-$ conversion
with sensitivity of $O(10^{-17})$


Current limit: $< 7 \times 10^{-13}$ (Au target)
SINDRUM II, Eur. Phys. J. C 47, 337–346 (2006)

- Utilizing the **pulsed proton beam** from J-PARC Main Ring
- **4 superconducting solenoids** for efficient capture and curved transport
 - *C-shape Transfer Solenoids*... diff from Mu2e
- **Al** stopping target to form muonic atoms
- Detector system optimized for 105 MeV/c electrons



COMET Phase-I


- Physics search with $SES \sim 10^{-15}$ with a *dedicated* detector
- Furthermore,
 - Measure muon beam characteristics to reduce beam-related syst. uncertainties
 - Validate detector performances for Phase-II
- B-fields from the solenoids are partially overlapped
→ integrated field control is one of the keys



Phase-I Detectors


Physics Run

- **CyDet** (drift chamber + trigger hodoscope)
 - 105 MeV/ c electron spectrum
- **CRV** (cosmic ray veto)
 - Surrounding whole detector + solenoid to cover 2π direction



Beam Measurement


- **StrECAL** (straw-tube tracker + LYSO calorimeter)
 - Reduce systematics, optimize *Phase-II* design



Proton Beam from J-PARC





Proton Beam from J-PARC



Proton Beam from J-PARC



J-PARC beam specification for COMET

- Bunched slow extraction
- Energy: 8 GeV (maximize backward emission)
- Extinction $\leq 1.02 \times 10^{-10}$ (90% C.L.)
- Measured at K1.8BR of the Hadron Facility (T78)







Pion Capture Solenoid (PCS)

- Capture pions **backward-emitted from Graphite** target with < 5 T field, guide muons/pions into MTS
- **Installed and connected with MTS in Dec. 2024**
 - Vacuum vessel deformation during evacuation: 1.2 mm at proton duct flange
 - Coil resistance & voltage withstand up to 500 V
 - Leak tests of LHe- & water-cooling pipes successful
- **Radiation tolerance** is needed (3.2 kW, 8 GeV beam)
 - Thick stainless shielding (~ 40 cm) protects coil
- **Excitation test after installation of return yokes and transfer tubes**





Muon Transport Solenoid (MTS)

- Select low-momentum muons ($\sim 40 \text{ MeV}/c$)
- Suppress background by curved transport
- Drift compensation with **dipole field** ($\sim 50 \text{ mT}$)
— a difference from Mu2e
- Performance is **verified** by measurement and simulation
 - On-axis solenoid field measured with **0.4% accuracy**







Phase- α : 1st beam commissioning

- Performed in 2023
- Measure the *proton beam profile* & *muon beam profile* after passing through the transport solenoid
- **Publication in prep.**



Bridge Solenoid (BS)

- Connects magnetic fields between MTS & DS
- Construction & excitation tests were completed without any problems
- Already connected with DS




Detector Solenoid (DS)



- Provide 1 T magnetic field to the detector
- Basic performance was successfully tested in 2024
— published: *IEEE TASC 36(3), 4500404 (2026)*.
- Cooled to **4.2 K** within **14 days** (with N₂ cooling)
- Ramped up to the rated current **without any training quenches**
- B-field mapping (10⁻⁴ acc.) will be measured in 2026
(now scheduling — detail in a following slide)



Delivered in KEK-Tsukuba in Sept. 2024



Magnetic Field Measurement System




Installation of DS

- Installation in the COMET Hall was completed in Nov. 2025
- Ready for the (integrated) B-field measurement and the detector installation!





<https://youtu.be/y7w5exfLMx4?si=9qHu7cPR23ywwz6BK>






B-Field Measurement

- Although a standalone field measurement was performed in 2024, a **precise and integrated measurement in the final experimental configuration is required.**
- Constructed a new *field mapper system* controlling rotation and keeping position tracking to achieve $O(10^{-4})$ T accuracy, and performance tests are ongoing
- **Installation to the DS will start soon**




CyDet — Physics Detector

- Consists of **Cylindrical Drift Chamber (CDC)** and **Cylindrical Trigger Hodoscope (CTH)**
- **CDC**: Momentum resolution **200 keV/c** (curvature)
 - *B-field measurement of DS is essential*
- **CTH**: 4-fold coincidences (as the first hardware trigger)




Cylindrical Drift Chamber (CDC)


- 20 concentric layers with 4,986 sense & 14,562 field wires
- 2084 L volume filled with He/iC₄H₁₀ (90:10)
- Basic performance test using CRs has been completed
 - (Overall) position resolution $\sim 200\ \mu\text{m}$ — expected level
 - Further analysis is ongoing (gas flow dependence, ...)
- Track Reco. studies with a high hit occupancy are ongoing




U-net deep-learning reconstruction scheme



Ryo Nagai (UOsaka)



Plastic scintillator (trigger)




17 June 2026

16

Gas Circulation System for CDC


Stable/safe CDC operation → *precise gas/pressure control*

- To reduce contribution from low- p particles, CDC inner wall is made of thin CFRP with a large radius → easy to buckle
- To keep proper performance + safety, careful design is needed
 - transient pressure-response analysis for each component is ongoing





CFRP 0.5 mm^t

Buckling risk > 350 Pa




Cylindrical Trigger Hodoscope (CTH)


- 10 mm^t/5 mm^t plastic scintillators (in total 256) located at the both ends of the CDC with a MPPC readout system
 - Trigger signals generated by 4 scintillators' coincidence
 - Tilt is tuned for the signal (105 MeV/c electrons)
- μ/e separation was measured in beam test with the prototype
- MPPC and Scintillator QC are ongoing
 - Completed: 300 for MPPCs ; 128(all of 10 mm^t)/256 for Scintillators



Ryo Nagai (UOsaka) NIM A 1067 (2024)169665




10 mm Scintillators' QC summary



Integration


- CTH frame was already manufactured
- CDC+CTH will be installed in a stainless-steel support structure
- This structure was constructed and now testing a scheme of the integration of CDC+CTH
- **The system is getting ready for installation!**




Cydet mount draft

Ryo Nagai (UOsaka)

CTH frame ▶




me



Support structure ▲



Cosmic Ray Veto Detectors



Large contribution from Cosmic Rays

CRV ensures >99.99% cosmic rejection — indispensable for COMET sensitivity.

- Nearly full coverage except the beam holes, using different technologies
 - Top/Side CRV: plastic scintillator layers (considering ARGO-RPC also)
 - Up/Downstream CRV: improved RPCs
- Scintillator CRV is **under construction**, and RPC-based CRVs are under development.



First module of the top CRV






StrECAL — Beam Measurement & Phase-II Prototype

- **Straw tracker:**


- 2,400 straws ($\phi 10$ mm, $20 \mu\text{m}$ aluminized Mylar), gas: Ar/C₂H₆ (50:50)
- (3/5) station completed, 4th/5th under construction
- Spatial resolution achieved $\sim 110 \mu\text{m}$ (prototype; req: $< 200 \mu\text{m}$)

- **Calorimeter:**

- Structure has been built: ready
- LYSO crystal (485/512) QC/QA ongoing (light yield, irradiation)
- APDs: all delivered; QA in progress
- Electronics: final version under refinement and validation



Phase-I Timeline



- Precise B-field meas will be performed soon
- Detector install planned this year
- Components ready for install

Phase-II Outlook

- Target SES $\sim 10^{-17}$ (**$\times 10,000$** beyond previous limits)
- Key Upgrades:
 - Introduce the **Electron Transport Solenoid**
— complete “double c-shape” curved geometry
 - Improve background suppression (cosmic ray veto, shielding)
 - Improve the detector and DAQ performance based on the Phase-I results

Summary

- COMET searches for $\mu^- \rightarrow e^-$ conversion using muonic atoms
- **Phase-I:** construction will be completed in ~ 1.5 years
→ **Physics run is planned to start in 2028** (target SES $\sim 10^{-15}$)
- **Phase-II:** target SES $\sim 10^{-17}$ with full transport solenoid system and better background suppression based on Phase-I results
- COMET can provide a leading probe of CLFV and New Physics scale up to $\sim 10^5$ TeV